

**TOWN OF TRUMBULL, CONNECTICUT  
REQUEST FOR PROPOSAL**

**NATATORIUM RENOVATIONS  
HILLCREST MIDDLE SCHOOL  
530 DANIELS FARM ROAD  
TRUMBULL, CONNECTICUT 06611**

**RFP #5948**

**DUE: JUNE 20, 2012 at 3:00PM**

**ADDENDUM 1**

---

This Addendum shall be part of the Contract Documents and modifies the original bidding documents. This Addendum is to be acknowledged by the bidders on the Bid Form. Failure to do so may subject the bidder to disqualification. **The bid date remains June 20, 2012.**

---

*It is the responsibility of the General Contractor to coordinate this work with all affected subcontractors. All parts and materials shall be included to complete the work and to properly integrate with adjacent work or existing conditions.*

**General Clarifications:**

- 1) The General Contractor is required to obtain all applicable permits, however the fees payable to the Town of Trumbull are waived.

**Changes to Bidding Requirements:**

- 1) Bid Proposal Form – Provide unit price per light fixture to dispose of PCB containing light ballast, mercury vapor bulbs, etc. as “Universal Waste” per the State of Connecticut disposal procedures.

**Changes to Drawings:**

- 1) **Drawing A-101 (Refer to notes on Reflected Ceiling Plan)**
  - a) Clarification regarding painting of new spray-applied cellulose insulation textured ceiling finish – Provide two coats of Benjamin Moore P42 epoxy coating. Color to match existing textured ceiling finish.
  - b) Clarification regarding painting of shower ceilings – Provide one coat of Benjamin Moore O23 primer and two coats of P42 epoxy coating on new and existing ceilings within shower rooms where structural work is taking place.
  - c) Clarification regarding painting of exposed conduits and pipes within Natatorium – Provide one coat of Benjamin Moore P07 Primer and two coats of P42 epoxy coating on new and existing conduits and pipes.
  - d) Clarification regarding removal and replacement of drywall ceilings in shower rooms – In addition to replacing drywall ceilings as required for the structural work, also replace ceilings as required for relocation of roof drains as shown on roof mechanical drawing.

END OF ADDENDUM #1