



Town of Trumbull, Connecticut

REMOVAL AND REPLACEMENT OF TOWN HALL ELEVATOR Trumbull, Connecticut

RFP #5955 DUE: November 14, 2012 at 3:00PM

ADDENDUM 2

This Addendum shall be part of the Contract Documents and modifies the original bidding documents. This Addendum is to be acknowledged by the bidders on the Bid Form. Failure to do so may subject the bidder to disqualification. **The bid date remains November 14, 2012 per Addendum #1.**

It is the responsibility of the General Contractor to coordinate this work with all affected subcontractors. All parts and materials shall be included to complete the work and to properly integrate with adjacent work or existing conditions.

Changes to Specifications:

1) Section 14210 – Electric Traction Elevators

- a.) Part 1.01 – A: Delete reference to retaining existing elevator frames and hoistway sills. Note: Entrance frames and sills to be removed and replaced with new as indicated on drawings and specified.

Changes to Drawings:

1) Drawing A-101

- a) Elevation / Section 4 & 5: Add the following note to top of hoistway – “ Provide (1) one hour fire rated horizontal shaft wall assembly at top of hoistway consisting of 4” C-H metal studs at 24” o.c. with 1” gypsum board shaft wall liner and 5/8” type X gypsum board per UL # U469”.

End of addendum 2