



TOWN OF TRUMBULL
REQUEST FOR QUOTATION (RFQ)

CONSTRUCTION OF SANITARY SEWERS
PHASE IV, PART B, CONTRACT 4

BID NUMBER 5795 (**REBID**)

DUE: May 20, 2009 3:00 PM

ADDENDUM 1 (REVISED)

THE PREVIOUS ADDENDUM 1 IS HEREBY DELETED AS FOLLOWS BELOW.
ALL ADDENDUMS MUST BE ACKNOWLEDGED AND NOTED ON THE BID
RESPONSE FORM.

~~A. The Contractor shall provide a regular log of compaction tests as the work progresses with grade depths at the direction of the Town Engineer. Compaction tests shall pass when they reach 95% compaction or more. The Owner shall pay for all compaction tests that pass. If the results of the compaction fail to reach 95% compaction, the cost for that test shall be paid for by the Contractor and the Contractor shall be responsible for re-working the area until the trench compaction achieves a passing grade. The Contractor is responsible for the cost of re-testing the failed area.~~

~~B. The cost of providing power for the Pump Station shall be a set price determined by the Power Company and assumed by the Contractor.~~

~~C. The following item shall be added to the Bid Items and included in the Total Bid Amount:~~

~~#69. 76,000 CY Trench Excavation Rock~~

~~1. _____
2. _____~~

A. Replace BID: Page 8 of 21 and BID: Page 9 of 21 with BID: Page 8 of 21 (rev. 05-12-09) and BID: Page 9 of 21 (rev. 05-12-09)
ATTACHED

B. Replace SPECIFICATION Page 2.5-6/7 with SPECIFICATION
Page 2.5-6/7 (rev. 05-12-09). ATTACHED

<u>Item</u>	<u>Approx. Quan. & Unit Meas.</u>	<u>Items With Unit Prices Written In Words</u>	<u>Unit Price Dollars & Cents</u>	<u>Extended Total</u>
62.	7765*LF.	18" CPP Storm Drainage (0-10') deep		
63.	300* LF.	24" CPP Storm Drainage (0-10') deep		
64.	14 Ea.	Test Pits		
65.	350 LF.	Stream, River & Culvert Crossing		
66.	13 Ea.	Core Drilling Existing Sanitary Manholes		
67.	38000 CY	Trench Excavation - Earth		
68.	38000 CY	Trench Excavation - Rock		
69.	15150 CY	Borrow		
70.	20000 CY	Gravel Fill		
71.	52800 SY	Temporary Bituminous Repair		
72.	324233SY	Permanent Pavement Repair <i>includes permanent bituminous concrete overlay</i>		
73.	50* Ea.	Frame Adjustment		

<u>Item</u>	<u>Approx. Quan. & Unit Meas.</u>	<u>Items With Unit Prices Written In Words</u>	<u>Unit Price Dollars & Cents</u>	<u>Extended Total</u>
74.	23500 LF*	Bituminous Curb (with back up grading)		
75.	1 L.S.	Restoration		
76.	2 Ea.	Project Sign		
77.	85635 L.F.	Television Pipeline Inspection		
78.	1 LS.	Pump Station - Complete		

TOTAL OF BID..... \$ _____

LUMP SUM PRICE (If applicable). \$ _____

Respectfully submitted:

Signature Address

Title Date

License Number (if applicable)

(SEAL - If Bid is by a corporation)

Attest _____

Quantities were modified by the Town based on previous experiences of new sanitary sewer installations in existing roads. The location and placement of these extra items not indicated on the drawings, if required, will be at the discretion of the Town Road Inspector in the field. Unit Prices will prevail.

DIVISION 2
SECTION 2.5

Compaction tests will pass when they reach 95% compaction or more as specifications require. Trenches that fail compaction tests will have the fill material removed to an elevation approximately 6 feet above the pipe. Trenches will be compacted and refilled in accordance with the backfill requirements stated. The compaction requirements apply to mainline trenches as well as all lateral trenches.

F. MEASUREMENT AND PAYMENT - No measurements or separate payment will be made for the Work under this section; its costs shall be included in the Prices bid for other items, except that if:

"Earth" is encountered below the proposed trench bottom and it's removal is ordered by the Engineer within the payment limits shown on the Contract Drawings.

Measurement for payment will be taken of the actual number of cubic yards of "earth" excavated as required to set pipe at proper grade as indicated on the Contract Drawings. The Contractor shall notify the Engineer a sufficient time ahead for the Engineer to schedule field measurements if he deems it necessary. If the Contractor fails to give such notice, the Engineer shall presume that the measurements taken at the time he first sees the material in question will give the true quantity of excavation.

"Earth" in trench excavation will be paid at the Unit Price per Cubic Yard at the depth classification for "Trench Excavation - Earth" as listed in the Bid Schedule. The Unit Price shall include the cost of all materials, equipment, tools and labor incidental to or necessary for completion of the Work. "Borrow" backfill material will be measured and paid for separately under its respective item.

2. "Rock" is encountered and it's removal within the payment limits shown on the Contract Drawings.

Measurement will be taken of the actual number of cubic yards of "rock" excavated as required to set pipe at proper grade as indicated on the Contract Drawings. The Contractor shall notify the Engineer a sufficient time ahead for the Engineer to schedule field measurements if he deems it necessary. If the Contractor fails to give such notice, the Engineer shall presume that the measurements taken at the time he first sees the material in question will give the true quantity of excavation.

"Rock" in trench excavation will be paid at the Unit Price per Cubic Yard at the depth classification for "Trench Excavation - Rock" as listed in the Bid Schedule. The Unit Price shall include the cost of all materials, equipment, tools and labor incidental to or necessary for completion of the Work. "Borrow" backfill material will be measured and paid for separately under its respective item.